Standard build

Production quantity: 10
Currency: USD

Item number	Item	Manufacturer	Manufacturer part number	Supplier	Supplier part number	Quantity per assembly	Quantity for production volume	Cost per item	Cost per assembly	Cost for production volume
1	floppy-coaster-panel-without-cutout.dxf 115.4mm x 118.9mm x 1.0mm Clear PETG	My design, laser cut by ponoko.com		My design, laser cut by ponoko.com		2	20	$1.03	$2.07	$20.66
2	floppy-coaster-panel-with-cutout.dxf 115.4mm x 118.9mm x 3.0mm Red Translucent Acrylic	My design, laser cut by ponoko.com		My design, laser cut by ponoko.com		1	10	$2.34	$2.34	$23.44
3	BUMPER CYLINDRICAL 0.5" DIA BLK	Keystone Electronics	720	DigiKey	36-720-ND	4	40	$0.26	$1.05	$10.48
4	M3 x 8 Phillips head screw	n/a	n/a	n/a	n/a	4	40	$0.05	$0.18	$1.82
5	M3 Nyloc nut	n/a	n/a	n/a	n/a	4	40	$0.04	$0.14	$1.41
6										
7										
8										
9										
10										

Total:		**$5.78**	**$57.81**
Average:		**$1.16**	**$11.56**

Alternate build

Production quantity: 10

Currency: USD

Item number	Item	Manufacturer	Manufacturer part number	Supplier	Supplier part number	Quantity per assembly	Quantity for production volume	Cost per item	Cost per assembly	Cost for production volume
1	floppy-coaster-panel-without-cutout.dxf 115.4mm x 118.9mm x 1.0mm Clear PETG	My design, laser cut by ponoko.com		My design, laser cut by ponoko.com		2	20	$1.03	$2.07	$20.66
2	floppy-coaster-panel-with-cutout.dxf 115.4mm x 118.9mm x 3.0mm Red Translucent Acrylic	My design, laser cut by ponoko.com		My design, laser cut by ponoko.com		1	10	$2.34	$2.34	$23.44
3	Floppy-coaster-panel-without-cutout.dxf 115.4mm x 118.9mm x 2.0mm Grey Acrylic Felt	My design, laser cut by ponoko.com		My design, laser cut by ponoko.com		1	10	1.06	$1.06	$10.60
4	Pop rivet	n/a	n/a	n/a	n/a	4	40	$0.03	$0.11	$1.09
5										
6										
7										
8										
9										
10										

Total: $5.58 $55.79

Average: $1.39 $13.95